



SCOPE OF WORKS

Main Step Old Material Removal

**Gulfstream, 79 Southside Road
Site# T102000**

Please provide a quotation to refurbish the landings, treads and risers at the central and southern end stairwells of the three- story Gulfstream building.

Pricing shall include

- **The labor to remove and discard old rubber flooring (landing) treads and risers.**
- **Prepare the surfaces by Grinding and rendering patches needed.**
- **Applying a Primer and Topcoat of Epoxy flooring paint over the landing, treads and risers**

Quotations must be emailed to christopherw@bhc.bm no later than 12:00 noon of Friday the 24^h of January 2025.

Please contact Christopher Wellman 705-8436 or christopherw@bhc.bm for any further information, viewing or queries regarding this scope of work.

TO CLEAN TIDY AND REMOVE ALL TRASH AND DEBRIS FROM THE SITE.

